Abstract estimate for Improving Saligame Halebid Road (constructing tunnels and causeways.)

| Items of work | Unit | Quantity |
|---|---|---|
| *Constructing two tannels of 1 vent of 4' × 6' at 6/11 and 1/12.* | | |
| Earthwork excavating foundation rockey soil... ... ... | C.yd. | 11 |
| Metal stone in surki mortar ... ... ... .. | ,, | 309 |
| Burnt stone in surki mortar with old stones ... .. ... | ,, | 766 |
| Surki pointing ... ... ... ... ... | Sqr. | 4·79 |
| Burnt stone slabs 6" thick edges dressed ... ... ... | ,, | 83 |
| Resetting old stones in mortar ... ... ... ... | ,, | 84 |
| Dismantling the existing sluice tunnel and levelling the ground ... | Lumpsum | |
| *Constructing two tunnels 3 vents of 4' × 5' at 5/10 and 5/12.* | | |
| Earthwork excavating foundation gravelly soil ... ... | C.yd. | 18 |
| Burnt brick in surki mortar .... ... ... ... | C.ft. | 1,571 |
| Surki plastering ... ... ... ... ... | Sqr. | 9·32 |
| Burnt stone slabs 6" thick edges dressed ... ... ... | ,, | 248 |
| Burnt stone slabs 3" to 4" set in mortar .. ... ... | ,, | 112 |
| Rough stone work new ... ... ... ... | C.yd. | 13 |
| *Constructing a tunnel of 1 vent of 3' x 3' at 3/13.* | | |
| Earthwork excavating gravelly soil ... ... ... | C.yd. | 12 |
| Burnt brick in surki mortar ... .. ... ... | C.ft. | 869 |
| Surki plastering ... ... ... ... ... | Sqr. | 3·1 |
| Burnt stone slabs 6" thick edges dressed ... ... ... | ,, | 66 |
| Burnt stone slabs 3" to 4" set in mortar ... ... ... | ,, | 80 |
| Rough stone work new ... ... ... ... | C.yd. | 4 |
| *Constructing two combined causeways and tunnels at 5/9 and 6/3.* | | |
| Earthwork excavation in clay ... ... ... ... | C.yd. | 22 |
| Burnt brick in surki mortar ... ... .. ... | C.ft. | 1,110 |
| Burnt stone slabs 6" thick edges dressed .. ... ... | Sqr. | 120 |
| Surki plastering .. ... ... ... ... | ,, | 5·83 |
| Rough stone work new ... .. ... ... | C.yd. | 45 |
| *Constructing a causeway 30 feet long at 2/15.* | | |
| Earthwork excavating stoney gravel ... ... ... | C.yd. | 3 |
| Burnt brick in surki mortar ... ... ... ... | C.ft. | 194 |
| Rough stone work new .. ... ... ... | C.yd. | 21 |
| Surki plastering ... ... ... ... ... | Sqr. | 90 |
| *Constructing senppers of 1 vent of 2' x 2' at 4/11, 7/11, 2/12, 2/18 and 5/18.* | | |
| Length of senppers required 4/11, 7/11, 2/12, 2/18 and 5/18 ... | 151 | 128 |

R. L. STEELE,
*Executive Engineer.*